

<b>Contract #:</b>		<b>01-13-14 ITQ</b>						
<b>Contract Title:</b>		Keystone Bridge Water Main Replacement - Bridge No. 2						
<b>Bid Opening Date:</b>		11/6/2013						
<b>Prepared By:</b>		Ruby C. Johnson						
		<b>EPOCA Corp</b>						
	FEIN #:	274700122						
	Address:	800 NE 125th Street						
	City / State/ Zip	North Miami, FL						
	Phone:	305.851.7100						
	Contact:	David Bradley						
	Email:	david@epocacorp.com						
	Local Preference Affirmed:	YES/LOCAL						
<b>#</b>	<b>Description</b>							
1	Keystone Bridge Water Main Replacement							
		Quantity	UOM	Unit Price	Extended Price			
1	Mobilization	1	LS	\$2,000.00	\$2,000.00			
2	Maintenance of Traffic (City will provide Police Officers). Ensure at a minimum one lane is open the entire duration of project. (include 2 flaggers and signs)	1	LS	\$2,000.00	\$2,000.00			
3	Removal of Exist. Asphalt pavement and limerock	55	CY	\$20.00	\$1,100.00			
4	8" Limerock base for road	12	CY	\$42.50	\$510.00			
5	S-3 Asphalt (2 lifts) -3" total trench restoration per MDC Standards. (inc. prime coat)	5	CY	\$450.00	\$2,250.00			
6	Furnish & install 60 LF of 8" C-900 PVC water main under bridge	60	LF	\$100.00	\$6,000.00			
7	(2) coats of paint to protect from UV rays under bridge. Contractor shall provide information regarding paint to be used	60	LF	\$100.00	\$6,000.00			
8	Solid Sleeve under south end of bridge	1	EA	\$1,000.00	\$1,000.00			
9	Furnish and install water main under road (with location tape and pipe bedding)	120	LF	\$170.00	\$20,400.00			
10	(3) -45 degree bends	3	EA	\$900.00	\$2,700.00			
11	Furnish & Install 8" Gate Valve (1) & traffic rated cover	1	EA	\$4,500.00	\$4,500.00			
12	Connect to Exist. Valve (Street Side)	1	LS	\$3,000.00	\$3,000.00			
13	Connect to exist. Pipe (Bridge-north side)	1	LS	\$3,000.00	\$3,000.00			
14	Remove and dispose exist. Water main (180 LF)	180	LF	\$10.00	\$1,800.00			
15	Furnish and Install (6) pipe supports under bridge (stainless steel)	6	EA	\$500.00	\$3,000.00			
16	(1) Sample Point with Box per MD Detail WS 3.10	1	EA	\$800.00	\$800.00			
17	120 LF Double yellow pavement marking (thermoplastic)	120	LF	\$2.70	\$324.00			
18	20 LF Stop bar (thermoplastic)	20	LF	\$40.00	\$800.00			
	<b>TOTAL</b>				<b>\$61,184.00</b>			
		<b>RECOMMENDED VENDOR</b>						