



ADDENDUM No. 1

MAY 31, 2018

Solicitation Title: Rehabilitation of Wastewater Pump Station No. 12 (San Souci III)

Solicitation No.: IFB 38-17-18 Opening Date: **MONDAY, JUNE 11, 2018**
BY NO LATER THAN 3:30 PM

Attention all potential bidders:

- MUST Addendum:** Read carefully and follow all instructions. Information included in this Addendum will have a material impact on the submittal for this solicitation. All "MUST" addenda are considered a matter of responsiveness. "MUST" addenda must be acknowledged on Form "A-5. Failure of a Submitter to acknowledge the addenda may be cause for rejection of the bid.

To all prospective bidders, please note the following changes and clarifications:

1. The deadline for submittal for proposals has been extended as follows:
SUBMITTAL DEADLINE:
~~WEDNESDAY, JUNE 6, 2018~~ **MONDAY, JUNE 11, 2018, BY NO LATER THAN 3:30 PM (LOCAL TIME)**
2. The Bid Form (page 28) is replaced with the Bid Form included as **Attachment "1"** of this addendum. Respondents must use the revised Bid Form as part of their bid submittal in order to be considered responsive.

Request for Information Questions/Clarification:

Q.1 "As per Section 2.0 Special Conditions, 2.3 Bidder Qualifications: The bidder shall have a valid State of Florida Certified General Contractor (GC License) **AND** Underground Utility and Excavation Contractor License.

We possess a State of Florida General Contractor's License and a Miami Dade County "General Engineering" License.

We respectfully request that the licensing requirements for this project be broaden to accept bidders with such licenses.

During the last 33 years our Company has constructed over 40 sewage lift stations including storm sewer pump stations for many Municipalities in both Broward County and Miami Dade County with our present Licenses. These municipal projects ranged in

size from \$300,000.00 to \$28 million. We are presently constructing lift stations for City of Fort Lauderdale, City of Coral Springs and City of Hollywood with our Licenses.

Our Company is FDOT Certified to construct lift stations and storm sewer pump stations. Refer to attached Certifications.

We hope that you will reconsider your licensing requirements for this project since this will prevent many qualified companies from bidding this project

- A.1** Respondents will be required to have both a General Contractor License and a Underground Utility and Excavation Contractor License. Licenses for sub-contractors shall be accepted as well.
- Q.2** “Regarding page 14 of 40 Section 2.0; line item 2.3 b, Is the contractor required to have both the State of Florida Certified General Contractor License and the Underground Utility and Excavation Contractor License in order to be a qualified bidder?”
- A.2** See A.1
- Q.3** “We intend to place a bid as the general contractor for this project and request you consider adding CC Control Corp. as an acceptable Control and Instrumentation contractor.”
- A.3** Respondents are responsible for qualifying their own subcontractors, suppliers, and materialmen, and ensuring that they are able to meet the performance and technical requirements contained in the Solicitation.
- Q.4** “After reviewing the bid form (Bid Tabulation form Page 29) I am a little concern for the following:
The Items No 37 and 39 are missing from the Bid Form (Bid Tabulation). Please advise.”
- A.4** Items 37 and 39 are not missing. The bid form is numbered incorrectly. Please see attached a corrected bid form.
- Q.5** “Is the city willing to accept Homa pump as “or equals” for this and the other two bids?”
- A.5** Alternate pumps will be accepted provided that they have the same technical data as shown on the plans and technical specifications and must be acceptable to the City’s Public Works Department.
- Q.6** “Will you please provide us a 1 1/2” Sump Pump Technical Equipment Data.”
- A.6** Please see plans included as Attachment “A” of the Solicitation. Sump pump shall be 1/3-horsepower, single phase, oil filled unit, with overload protection. Unit shall be Series BP27, by Barnes, or approved equal.
- Q.7** “Provide Technical information from Electromagnetic Flow Meter and Pressure Transmitter requested at the project mentioned above (IFB# 37-17-18 Rehabilitation of Wastewater Pump Station No 10 (San SOUCI I)).”
- A.7** Please refer to plan sheet E-2.6 “Typical Control Panel Layout and Details” included as Attachment “A” of the Solicitation.
- Q.8** “Is there a Pre- Bid meeting Scheduled?”
- A.8** No, there is no pre-bid meeting for this Solicitation.
- Q.9** “What is the engineering estimated budget?”
- A.9** This information can be found on the cover page of the Solicitation.

Q.10 “Is there a bid bond form for the project?”

A.10 Yes, all contract forms can be found on the Purchasing Department’s website. A direct link to these forms can be found on page 3 of the Solicitation

For any other questions, clarification can be found in the specifications.
All other terms, conditions and specifications remain unchanged for this solicitation.

End of Addendum



Attachment “1”

Revised Bid Form



REVISED BID FORM

**Rehabilitation of Wastewater Pump Station No. 12
(San Souci III)
IFB No. 38-17-18**

The proposed price shall include the total cost for materials, labor, supervision, equipment, permits, overhead and profit, bonds and insurance, and all other related expenses needed to successfully execute the Project described under this Solicitation and referenced documents.

ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
1	TEMPORARY CONTROLS (SWPPP)	LS	1	\$	\$
2	CLEARING & GRUBBING, TREE REMOVAL	LS	1	\$	\$
3	EXCAVATION	LS	1	\$	\$
4	DEWATERING ALLOWANCE	LS	1	\$ N/A	\$ 20,000.00
5	TEST HOLE ALLOWANCE	EA	4	\$ N/A	\$ 500.00
6	FURNISH AND INSTALL TEMPORARY BYPASS ALLOWANCE	LS	1	\$ N/A	\$ 30,000.00
7	FURNISH AND INSTALL 8' DIAMETER WET WELL WITH ALLUMINIUM ACCESS HATCH, PUMPS, MOUNTING PLATES AND HARDWARE AND ASSOCIATED APPURTENANCES EXCLUDING FORCE MAIN PIPING AND FITTINGS)	LS	1	\$	\$
8	FURNISH AND INSTALL 4" DI VENT WITH VENT CAP AN SS SCREEN. 3" SCH 40 PVC FLOOR DRAIN WITH P-TRAP/PROPOSED PIPE SUPPORT/SS PRESSURE GAUGE.	LS	1	\$	\$
9	FURNISH AND INSTALL NEW VALVE VAULT WITH ALUMINIUM ACCESS HATCH (EXCLUDING FORCE MAIN PIPING AND FITTINGS)	LS	1	\$	\$
10	FURNISH AND INSTALL NEW METER VAULT WITH ALUMINIUM ACCESS HATCH (EXCLUDING FORCE MAIN PIPING AND FITTINGS)	LS	1	\$	\$
11	GROUT WORK	LS	1	\$	\$
12	FURNISH AND INSTALL 6" DUCTILE IRON PIPE (D.I.P) INCLUDES ALL INSTALLATION COMPONENTS	LF	40	\$	\$
13	FURNISH AND INSTALL 8" DUCTILE IRON PIPE (D.I.P) INCLUDES ALL INSTALLATION COMPONENTS	LF	80	\$	\$
14	FURNISH AND INSTALL 8" POLYVINYL CHLORIDE PIPE (P.V.C) INCLUDES ALL INSTALLATION COMPONENTS	LF	265	\$	\$
15	FURNISH AND INSTALL 8"X8" ADAPTER SLEEVE INCLUDING ALL INSTALLATION COMPONENTS	EA	2	\$	\$

16	FURNISH AND INSTALL 8"X8" DIP TEES INCLUDING ALL INSTALLATION COMPONENTS	EA	2	\$	\$
17	FURNISH AND INSTALL 8" DUCTILE IRON ELBOW (REST), INCLUDING ALL INSTALLATION COMPONENTS	EA	9	\$	\$
18	FURNISH AND INSTALL 8" PLUG VALVE, INCLUDES ALL INSTALLATION COMPONENTS	EA	5	\$	\$
19	FURNISH AND INSTALL 8" CHECK VALVE, INCLUDES ALL INSTALLATION COMPONENTS	EA	2	\$	\$
20	FURNISH AND INSTALL 4" CAP, INCLUDES ALL INSTALLATION COMPONENTS	EA	2	\$	\$
21	FURNISH AND INSTALL 8" CAP, INCLUDES ALL INSTALLATION COMPONENTS	EA	6	\$	\$
22	FURNISH AND INSTALL 6"X8" D.I.P ECCENTRIC ENLARGER, INCLUDING ALL INSTALLATION COMPONENTS	EA	2	\$	\$
23	FURNISH AND INSTALL AUTOMATIC AIR RELEASE VALVE, INCLUDES ALL INSTALLATION COMPONENTS INCLUDING STRUCTURE, SADDLE, VALVES AND FITTINGS.	EA	1	\$	\$
24	REMOVE EXIST MANHOLE	EA	1	\$	\$
25	FURNISH AND INSTALL MANHOLE	EA	3	\$	\$
26	FURNISH AND INSTALL 1 1/2" SUMP DISCHARGE PIPE, INCLUDES ALL INSTALLATION COMPONENTS	LF	60	\$	\$
27	FURNISH AND INSTALL SUMP PUMP	EA	2	\$	\$
28	FURNISH, INSTALL AND CONNECT 2' PE PIPE, INCLUDING FITTINGS, 2 BALL VALVES, PROPOSED WATER METER, BACKFLOW PREVENTER 3/4-INCH	LS	1	\$	\$
29	COATING FOR WET WELL AND VALVE VAULT	LS	1	\$	\$
30	FURNISH AND INSTALL TYPE F INLET	EA	2	\$	\$
31	FURNISH AND INSTALL 18" (HPDE) STORM SEWER SOLID PIPE, INCLUDES ALL INSTALLATION COMPONENTS (COST INCLUDES 4 FEET TRENCH AND EXCAVATION AND BACKFILL)	LF	35	\$	\$
32	FURNISH AND PLACE 6" CONCRETE	SY	35	\$	\$
33	MILLING 3/4-INCH EXISTING ASPHALT	SY	950	\$	\$
34	FURNISH AND PLACE ASPHALT CONCRETE PAVEMENT	TN	72	\$	\$
35	FURNISH AND PLACE 8" LIMEROCK BASE MATERIAL	SY	400	\$	\$
36	COMPACTION STABILIZATION OF 12" SUBGRADE	SY	460	\$	\$
37	REMOVE EXIST SIDEWALK	SY	73	\$	\$
38	REMOVE EXIST CURB & GUTTER	LF	170	\$	\$
39	FURNISH AND INSTALL CURB & GUTTER	LF	170	\$	\$

40	FURNISH AND INSTALL 6-FOOT HIGH CHAIN LINK FENCE AND GATES	LF	200	\$	\$
41	FURNISH AND INSTALL TOPSOIL AND SOD	SY	180	\$	\$
42	FURNISH AND INSTALL FILL	SY	180	\$	\$
43	CUT AND REMOVE PIPE	LF	210	\$	\$
44	GROUT, FILL AND ABANDON PIPE	LF	130	\$	\$
45	FURNISH AND INSTALL POST SIGNS	EA	2	\$	\$
46	METER CAN	EA	1	\$	\$
47	SERVICE MAIN DISCONNECT SWITCH	EA	1	\$	\$
48	5 KVA CONTROL TRANSFORMER	EA	1	\$	\$
49	PUMP STATION CONTROL PANEL	EA	1	\$	\$
50	CONDUITS, VARIOUS	LS	1	\$	\$
51	POWER WIRING VARIOUS	LS	1	\$	\$
52	SIGNAL AND CONTROL WIRING, VARIOUS	LS	1	\$	\$
53	EXPLOSIVE PROOF CONDUIT SEAL	EA	5	\$	\$
54	GROUNDING	LS	1	\$	\$
55	MOUNTING SUPPORT	LS	1	\$	\$
56	JUNCTION BOXES RECEPTACLE, FLOATS, MISC.	LS	1	\$	\$
57	LEVEL TRANSMITTER	EA	1	\$	\$
58	PRESSURE TRANSMITTER	EA	1	\$	\$
59	RTU ANTENNA POLE, FOUNDATION AND HARDWARE	LS	1	\$	\$
60	DIRECTIONAL BORED CONDUIT PROVIDED BY FPL	LF	100	\$	\$
61	INSTALLATION OF FPL PROVIDED TRANSFORMER PAD	LS	1	\$	\$
62	FLOW METER	LS	1	\$	\$
63	CONCRETE (3000 PSI)	CY	12.5	\$	\$
64	REINFORCING STEEL (G-60)	LB	132	\$	\$
65	WELDED WIRE FABRIC (6"X6"-W1.4XW1.4)	SF	336.3	\$	\$
66	HANDRAIL (GALVANIZED POST)	LF	54	\$	\$
SUBTOTAL BID AMOUNT (ITEMS 1-66)					\$

67	GENERAL REQUIREMENTS & CONDITIONS (INCLUDES BONDS & INSURANCE, SUPERVISION, TEMPORARY FACILITIES, ETC.)	5% OF SUBTOTAL BID AMOUNT	\$
68	MOBILIZATION & DEMOBILIZATION	5% OF SUBTOTAL BID AMOUNT	\$
69	MAINTENANCE OF TRAFFIC (MOT)	5% OF SUBTOTAL BID AMOUNT	\$
70	CONTINGENCY	10% OF SUBTOTAL BID AMOUNT	\$
71	PERMIT FEE (ALLOWANCE)	LUMP SUM	\$ 5,000.00
TOTAL BID AMOUNT			

[See Next Page for Notes and Acknowledgement]

NOTES:

- Please note that the City has added a Permit Allowance to cover the cost of permits issued for each project performed under this Contract; therefore, Respondents should not include the cost of permitting as a separate part of their proposed price.
- The Respondent acknowledges that the Project must be completed within **two hundred and twenty-five (225) calendar days** from the City's issuance of a Notice-to-Proceed.
- Respondent(s), individual, partnership, corporation or association responding to this Solicitation certifies that all statements made in this document are true and correct to the best of their knowledge. Moreover, the Respondent(s) agrees to hold this offer open for a period of ninety (90) days from Bid Opening.
- Respondent(s) understand and agree to be bound by the conditions included in this Solicitation and shall comply with all requirements contained therein.

Company Name

Authorized Company Representative (Print Name)

Title:

Signature

Date: